PRICE SCHEDULE

Name of the Work: Work of providing and laying GI pipe for facilitate the drinking water to colony at T.K.Halli.

Sl No	Particulars	Unit	Qty	Unit rates to be quoted	
				In figures	In words
1	Earth work excavation for pipelines/cables by Manual means upto 600 mm trench width, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, including dressing of excavated surfaces, disposing off or leveling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m. Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering and lift upto 1.5 m including cost of labour, tools, usage& other appurtenances required to complete the workIn all kinds of soil depth upto 1.5m	m^3	198		
2	Providing, Laying and Fixing GI pipes conforming to IS 1239:1990 with latest amendments complete with GI fittings (excluding the cost of fittings) with cuts and threads wherever necessary, including testing for water tightness, with all lead and commissioning. (Contractor will make his own arrangements for procuring water for testing) Heavy duty GI pipe of 100mm dia.	m	1100		
3	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications.	m3	110		
4	100 mm dia GM (Copper alloy) Gate valves.	each	10		
5	100 mm dia GI BEND.	each	30		
6	100 mm dia GI collar.	kg	50		
7	100 mm dia GI TEE.	each	20		

8	Labour charges for laying and jointing GI pipes with earth work including fixing collar, elbows,bends etc.,	m	1100		

Terms and Conditions:

1 All the works should be carried out as per KPPP Act and as per specification or as directed by the Engineer- in-charge.

2 Rates quoted above are including clearance of the site (prior to commencement of work and its completion) in all conditions of site, moisture, weather etc.

3 The Board reserves the right to bifurcate the work and entrust if warranted and if found expedient and advantageous to the Board of lowest approved rates.

4 The BWSSB reserves the right to accept or reject any OR all of the tenders without assigning any reason.

5 Rates should be inclusive of all taxes, insurance and freight charges.

6 Rates should be quoted by the contractor/firm on Item war basis both in figures and in words.

7 The payment will be made after completion of work.

8 The firm should upload turnover certificate which is counter signed by chartered accountant.

9 The firm should have requisite man power, machineries at their disposal to complete the work within the stipulated period, the necessary documents should be enclosed.

10 The firm has to upload "Form of tender" in the standard format or otherwise the tender will be liable for rejection.

11 ~~Rates are exclusive of GST & other taxes & duties~~.

"Approved"

Signature of the Contractor

DTP from page no 0 to (35) colony with price schedule for the "work of providing & laying of GI Pipe for facilitate the drinking water to colony at T.K.Halli" is Approved as corrected.

B.K.

Executive Engineer
Kaveri(Operation & Maintenance)-1 Division,
BWSSB, T.K.Halli.

Additional Chief Engineer
(Kaveri-O&M)-1,
Bangalore Water Supply
and Sewerage Board
Harohalli, Ramanagara Dist.-562 112

Chief Engineer
(Kaveri - Operation & Maintainance)
BWSSB, 6th Floor,
Cauvery Bhavan, K.G. Road,
Bengaluru - 560 009